TxDOT PEDESTRIAN SAFETY IMPROVEMENT PROJECT.

FM 60 (UNIVERSITY DRIVE)
PROJECT ID: 050601091
FROM: WELLBORN ROAD
TO: COLLEGE MAIN

PARTNERING WITH:
THE CITY OF COLLEGE STATION, AND
TEXAS A&M UNIVERSITY

STAKEHOLDER MEETING
WHERE:
THE TRADITION AT NORTHGATE DORMITORY
WHEN:
JANUARY 5, 2010, 5:00 PM

TxDOT PLANNING DOCUMENT
PRELIMINARY & SUBJECT TO REVISION.

PROPOSED GUTTER MAIN TYPICAL SECTION

NO OBSTACLES FOR EMERGENCY VEHICLE ACCESS

CHURCH AVE.

PATRICIA ST.

FM 2154 (WELLBORN RD.)

1ST ST.

BOYETT ST.

COLLEGE MAIN

TAMUS ST.

FM 60 (UNIVERSITY DR.)

EXISTING PARKING TO BE CREATED FROM 7 SPACES TO 9 SPACES TO ACCOMMODATE SIGNALIZED INTERSECTION. MAX 2 HR PARKING. TIMES TO BE DETERMINED BASED UPON USE.

EXISTING PARKING TO BE CHANGED TO NO PARKING, LOADING ZONE. TIMES TO BE DETERMINED BASED UPON USE.

EXISTING PARKING TO BE CHANGED TO "NO PARKING, LOADING ZONE". TIMES TO BE DETERMINED BASED UPON USE.

EXISTING PARKING TO BE CHANGED TO "NO PARKING, LOADING ZONE". TIMES TO BE DETERMINED BASED UPON USE.

EXISTING PARKING TO BE CHANGED TO "NO PARKING, LOADING ZONE". TIMES TO BE DETERMINED BASED UPON USE.

EXISTING PARKING TO BE CHANGED TO "NO PARKING, LOADING ZONE". TIMES TO BE DETERMINED BASED UPON USE.

EXISTING PARKING TO REMAIN, 188 FT, 4 SPACES, 20 FT/SPACE, ASPHALT SURFACE

EXISTING PARKING TO BE CHANGED TO "NO PARKING, LOADING ZONE". TIMES TO BE DETERMINED BASED UPON USE.

EXISTING PARKING TO REMAIN, 188 FT, 4 SPACES, 20 FT/SPACE, ASPHALT SURFACE

4" RAISED CONCRETE MEDIAN

6 IN CURBED ISLAND (TYP.)

6 FT PEDESTRIAN ZONE (TYP.)

REMAIN EXISTING SIDEWALK TO REMAIN

2% MAX BIKE LANE

4" 6 IN DIA REMOVABLE BOLLARDS

5 FT EXISTING SIDEWALK TO REMAIN (TYP.)

4 IN RAISED CONCRETE MEDIAN (TYP.)

4 FT EXISTING SIDEWALK TO REMAIN (TYP.)

2 FT CONCRETE GUTTER (FLUSH)

4" 6 IN DIA REMOVABLE BOLLARDS

10 FT EXISTING SIDEWALK TO REMAIN (TYP.)

4 FT EXISTING SIDEWALK TO REMAIN (TYP.)

EXTEND EXISTING SIDEWALK TO REMAIN

CURB EXTENSION WITH 6 INCH CURB

EXISTING PARKING TO REMAIN, 188 FT, 4 SPACES, 20 FT/SPACE, ASPHALT SURFACE

2 FT CONCRETE GUTTER

EXISTING PARKING TO REMAIN

HOUSTON ST. (EXTEND TAMU WALL)

REMOVE PART OF TAMU WALL

EXISTING PARKING:
90° PARKING
24' LANE (TWO-WAY TRAFFIC)
2 ACCESSIBLE PARKING SPACES
24 NORMAL PARKING SPACES

PROPOSED PARKING:
90° PARKING
24' LANE (TWO-WAY TRAFFIC)
2 ACCESSIBLE PARKING SPACES
18 NORMAL PARKING SPACES

- NO NORTHBOUND HOUSTON ST. (MUST ACCESS UNIVERSITY DR VIA HOGG ST & ASBURY ST).
- SOUTHBOUND HOUSTON ST HAS COMPLETE ACCESS TO CAMPUS (NO GATES OR RESTRICTIONS).
- PART OF EXISTING TAMU WALL MUST BE REMOVED.
- POST OFFICE LOT REMAINS WITHIN THE SAME FOOTPRINT BUT WITH FEWER SPACES.
- FIVE TREES REMOVED (15" MAX).
- 1.07 ACRES OF GREEN SPACE.

HOGG ST.

ASBURY ST.